## MYSORE DIVISION.

*Notice dated 25th September 1928.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 3 P.M., on 20th October 1928, for constructing in-patient ward attached to Local Fund Dispensary at Malvalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

| Description of work | Unit of work | Rate per unit |
|---|---|---|
| | | |

4. Each tender must be accompanied by a deposit of Rupees two hundred only (Rs. 200) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing in-patient ward attached to Local Fund Dispensary at Malvalli, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be noted for each items of work.

Estimate (Abstract) for constructing an in-patient ward in the dispensary compound at Malvalli.

| Sl. No. | Items of work | Per | Quantity |
|---|---|---|---|
| 1 | Earthwork excavation and filling in basement ... ... | C.yd. | 65 |
| 2 | Chunam concrete in foundation ... ... | C.ft. | 436 |
| 3 | Size-stone in mortar foundation ... ... | „ | 1,033 |
| 4 | Burnt brick in mud superstructure ... ... | „ | 1,598 |
| 5a | Do in chunam ... ... | „ | 198 |
| b | Do arch work ... ... | „ | 7 |
| 6 | Flooring with Cadapha slab and first class Mangalore tiles including cement pointing over a bed of concrete. | Sqr. | 4·75 |
| 7 | Teakwood wrought and put up .. ... | C.ft. | 49·57 |
| 8 | Burnt-stone slabs dressed and fixed ½" thick ... ... | S.ft. | 311 |
| 9 | Teakwood panelled door with bolts and hinges, etc., complete. | „ | 45·50 |
| 10 | Teakwood battened door with hinges, etc., complete ... | „ | 117·50 |
| 11 | Teakwood windows with glazed shutters inside and panelled shutters outside with iron bars, etc., complete. | „ | 48 |
| 12 | Teakwood battened windows with iron bars, etc., complete. | „ | 12 |
| 13 | Sun shades to windows with teak-wood ... ... | each | 2 |
| 14 | Teakwood finials .. ... | do | 2 |
| 15 | Constructing sinks of masonry in the rear ... .. | do | 2 |
| 16 | Ornamental eave board new ¾" wide .. ... | R.ft. | 132 |
| 17 | Roofing with first class Mangalore tiles over teak reepers, etc., complete. | Sqr. | 11·47 |
| 18 | Ridge tiles set in mortar and pointed with cement. ... | R.ft. | 31 |
| 19 | Plastering with chunnam ... ... | Sqr. | 32·85 |

| Sl. No. | Items of work | Per | Quantity |
|---|---|---|---|
| 20 | White and colour washing ... .. | Sqr. | 32·85 |
| 21 | Chocolate painting to doors and windows ... | ,, | 4·46 |
| 22 | Wood-oiling to rafters and collars ... | ,, | 4·00 |
| 23 | Chunam pointing to basement and plinth with hard ground morts and centring the joints. | Sqrs. | 1·68 |
| 24 | Clearing the site and levelling the ground and unforeseen charges. | L. S. | L. sum |
| 25 | Improving the flooring of Dispensary by removing the old-flooring tiles. | Sqr. | 2·80 |
| 26 | Flooring with first class 9" square Mangalore tiles on concrete bed with pointing. | ,, | 2·80 |

N. G. KRISHNA IYENGAR,
*Executive Engineer.*

## MYSORE RAILWAYS.

*Abstract Notification dated 21st September 1928.*

Attention of the intending contractors is hereby invited to the notice calling for tenders for providing additional accommodation for the Railway Dispensary and the Assistant Surgeon's Quarters near Mysore Railway Station, published in pages 965-966 of Part VI of the *Mysore Gazette*, dated 20th September 1928. Tenders will be received any day up to 2 P.M. of 15th October 1928.

M. RAMAIYA,
*Executive Engineer.*

## HASSAN DIVISION.

*Notice dated 24th September 1928.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M., 12th October 1928, for Extending Feeder Channel of Bagur Tank, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

| Description of work | Unit of work | Rate per unit |
|---|---|---|
| | | |

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the Feeder Channel of Bagur Tank, Channarayapatna Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.